Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
				1	90.00		0.60		54.00		
			Cor Culverts								
				2	7.00		0.60		8.40		
				2x2	7.00			0.25	7.00		
				2x2	1.80			0.25	1.80		
				2x4x9	30.00			0.30	648.00		
				2x4	20.00			0.30	48.00		
				2x9	30.00		0.60		324.00		
				2	20.00		0.60		24.00		
				4x9	30.00			0.15	162.00		
				4	20.00			0.15	12.00		
									1759.24	299.60	**527068.30**
26	KSRRB 300-47: scarifying kankar/ gravel/ metal crust upto 150mm thick with pick axes and disposal of stuff within a lead of 100 meters including cost of all labour charges complete as per specifications MORTH chapter 3, **No. 146 / Item No. 19.53 / PWD SR 2015-16**	Sqm									
			Durga Temple Road								
					0.00	1.00					
					15.00	1.00	1.00		15.00		
					15.00	1.20	1.10		16.50		
					15.00	1.50	1.35		20.25		
					15.00	1.20	1.35		20.25		
					15.00	1.35	1.28		19.13		
					15.00	1.20	1.28		19.13		
					15.00	1.20	1.20		18.00		
					15.00	1.25	1.23		18.38		
					15.00	1.20	1.23		18.38		
					15.00	1.00	1.10		16.50		
					15.00	1.20	1.10		16.50		
					15.00	1.00	1.10		16.50		
					15.00	1.20	1.10		16.50		
					15.00	1.00	1.10		16.50		
					15.00	1.00	1.00		15.00		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	1.00	1.00		15.00		
					15.00	1.20	1.10		16.50		
					15.00	1.20	1.20		18.00		
					28.30	1.10	1.15		32.55		
			Basavasamithi layout								
			2nd 'A' cross		0.00	1.00					
					15.00	1.20	1.10		16.50		
					15.00	0.95	1.08		16.13		
					15.00	0.90	0.93		13.88		
					15.00	0.90	0.90		13.50		
					15.00	0.90	0.90		13.50		
					22.20	0.90	0.90		19.98		
			2nd 'B' cross		0.00	4.20					
					15.00	4.90	4.55		68.25		
					15.00	4.60	4.75		71.25		
					15.00	3.90	4.25		63.75		
					15.00	4.90	4.40		66.00		
					18.00	5.70	5.30		95.40		
			2nd 'C' cross		0.00	5.00					
					15.00	5.10	5.05		75.75		
					15.00	4.90	5.00		75.00		
					15.00	4.90	4.90		73.50		
					15.00	5.40	5.15		77.25		
					15.50	5.20	5.30		82.15		
			2nd 'D' cross		0.00	4.00					
					15.00	4.20	4.10		61.50		
					15.00	4.20	4.20		63.00		
					15.00	4.40	4.30		64.50		
					15.00	5.00	4.70		70.50		
					18.00	5.40	5.20		93.60		
			2nd cross road(West side)		0.00	5.20					
					15.00	5.20	5.20		78.00		
					15.00	5.00	5.10		76.50		
					15.00	5.25	5.13		76.88		
					15.00	5.00	5.13		76.88		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	4.70	4.85		72.75		
					17.80	5.20	4.95		88.11		
			2nd cross road(East side)		0.00	5.00					
					15.00	5.00	5.00		75.00		
					15.00	4.80	4.90		73.50		
					15.30	5.40	5.10		78.03		
			L.G.Enclave layout								
			Main Road		0.00	5.70			0.00		
					15.00	5.50	5.60		84.00		
					15.00	6.00	5.75		86.25		
					15.00	5.40	5.70		85.50		
					15.00	5.70	5.55		83.25		
					15.00	6.20	5.95		89.25		
					15.00	6.10	6.15		92.25		
					15.00	5.50	5.80		87.00		
					15.00	6.20	5.85		87.75		
					15.00	6.40	6.30		94.50		
					15.00	5.60	6.00		90.00		
					15.00	6.10	5.85		87.75		
					15.00	6.00	6.05		90.75		
					15.00	6.00	6.00		90.00		
					28.10	6.70	6.35		178.44		
			1st cross		0.00	1.00			0.00		
				2	15.00	0.90	0.95		28.50		
				2	15.00	0.95	0.93		27.75		
				2	23.00	1.00	0.98		44.85		
			2nd cross		0.00	1.00			0.00		
				2	15.00	1.00	1.00		30.00		
				2	15.00	1.20	1.10		33.00		
				2	20.70	1.50	1.35		55.89		
			3rd cross		0.00	1.00			0.00		
				2	15.00	1.20	1.10		33.00		
				2	15.00	1.20	1.20		36.00		
				2	27.50	1.00	1.10		60.50		
			Ganesh layout Main road								
					0.00	5.80					

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	6.80	6.30		94.50		
					15.00	6.50	6.65		99.75		
					15.00	5.40	5.95		89.25		
					4.00	4.80	5.10		20.40		
					0.00	19.20					
					8.80	17.00	18.10		159.28		
					0.00	17.00			0.00		
					15.00	13.60	15.30		229.50		
					15.00	9.50	11.55		173.25		
					15.00	6.70	8.10		121.50		
					15.00	7.70	7.20		108.00		
					0.00	7.70					
					5.40	7.90	7.80		42.12		
					2.50	5.90	6.90		17.25		
					15.00	4.80	5.35		80.25		
					8.30	4.90	4.85		40.26		
					0.00	4.90					
					11.00	7.30	6.10		67.10		
					15.00	4.10	5.70		85.50		
					15.00	4.80	4.45		66.75		
					15.00	4.80	4.80		72.00		
					15.00	4.90	4.85		72.75		
					12.00	7.50	6.20		74.40		
					0.00	7.50					
					15.00	4.00	5.75		86.25		
					15.00	5.40	4.70		70.50		
					15.00	4.30	4.85		72.75		
					15.00	5.50	4.90		73.50		
					15.00	6.20	5.85		87.75		
					15.00	4.70	5.45		81.75		
					15.00	4.70	4.70		70.50		
					15.00	4.70	4.70		70.50		
					15.00	4.60	4.65		69.75		
					15.00	5.40	5.00		75.00		
					5.40	7.30	6.35		34.29		
									6417.59		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
									5947.63	25.32	**150594.00**
									469.96	25.89	**12167.00**
27	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to **wet mix macadam** specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification NO. 406, **Page No. 157 / Item No. 20.18 / PWD SR 2015-16**	Cum									
			Durga Temple Road								
					0.00	1.00					
					15.00	1.00	1.00	0.23	3.45		
					15.00	1.20	1.10	0.23	3.80		
					15.00	1.50	1.35	0.23	4.66		
					15.00	1.20	1.35	0.23	4.66		
					15.00	1.35	1.28	0.23	4.40		
					15.00	1.20	1.28	0.23	4.40		
					15.00	1.20	1.20	0.23	4.14		
					15.00	1.25	1.23	0.23	4.23		
					15.00	1.20	1.23	0.23	4.23		
					15.00	1.00	1.10	0.23	3.80		
					15.00	1.20	1.10	0.23	3.80		
					15.00	1.00	1.10	0.23	3.80		
					15.00	0.95	0.98	0.23	3.36		
					15.00	0.90	0.93	0.23	3.19		
					15.00	1.00	0.95	0.23	3.28		
					15.00	1.00	1.00	0.23	3.45		
					15.00	0.95	0.98	0.23	3.36		
					15.00	1.20	1.08	0.23	3.71		
					28.30	1.10	1.15	0.23	7.49		
			Basavasamithi layout								

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
			2nd 'A' cross		0.00	0.95					
					15.00	0.90	0.93	0.23	3.19		
					15.00	0.80	0.85	0.23	2.93		
					15.00	0.90	0.85	0.23	2.93		
					15.00	0.95	0.93	0.23	3.19		
					15.00	0.90	0.93	0.23	3.19		
					22.20	0.90	0.90	0.23	4.60		
			2nd 'B' cross		0.00	4.20					
					15.00	4.90	4.55	0.23	15.70		
					15.00	4.60	4.75	0.23	16.39		
					15.00	3.90	4.25	0.23	14.66		
					15.00	4.90	4.40	0.23	15.18		
					18.00	5.70	5.30	0.23	21.94		
			2nd 'C' cross		0.00	5.00					
					15.00	5.10	5.05	0.23	17.42		
					15.00	4.90	5.00	0.23	17.25		
					15.00	4.90	4.90	0.23	16.91		
					15.00	5.40	5.15	0.23	17.77		
					15.50	5.20	5.30	0.23	18.89		
			2nd 'D' cross		0.00	4.00					
					15.00	4.20	4.10	0.23	14.15		
					15.00	4.20	4.20	0.23	14.49		
					15.00	4.40	4.30	0.23	14.84		
					15.00	5.00	4.70	0.23	16.22		
					18.00	5.40	5.20	0.23	21.53		
			2nd cross road(West side)		0.00	5.20					
					15.00	5.20	5.20	0.23	17.94		
					15.00	5.00	5.10	0.23	17.60		
					15.00	5.25	5.13	0.23	17.68		
					15.00	5.00	5.13	0.23	17.68		
					15.00	4.70	4.85	0.23	16.73		
					17.80	5.20	4.95	0.23	20.27		
			2nd cross road(East side)		0.00	5.00					
					15.00	5.00	5.00	0.23	17.25		
					15.00	4.80	4.90	0.23	16.91		
					15.30	5.40	5.10	0.23	17.95		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
			L.G.Enclave layout								
			Main Road		0.00	5.70		0.23	0.00		
					15.00	5.50	5.60	0.23	19.32		
					15.00	6.00	5.75	0.23	19.84		
					15.00	5.40	5.70	0.23	19.67		
					15.00	5.70	5.55	0.23	19.15		
					15.00	6.20	5.95	0.23	20.53		
					15.00	6.10	6.15	0.23	21.22		
					15.00	5.50	5.80	0.23	20.01		
					15.00	6.20	5.85	0.23	20.18		
					15.00	6.40	6.30	0.23	21.74		
					15.00	5.60	6.00	0.23	20.70		
					15.00	6.10	5.85	0.23	20.18		
					15.00	6.00	6.05	0.23	20.87		
					15.00	6.00	6.00	0.23	20.70		
					28.10	6.70	6.35	0.23	41.04		
			1st cross		0.00	1.00			0.00		
				2	15.00	0.95	0.98	0.23	6.73		
				2	15.00	1.00	0.98	0.23	6.73		
				2	23.00	1.00	1.00	0.23	10.58		
			2nd cross		0.00	95.00			0.00		
				2	15.00	0.90	47.95	0.23	330.86		
				2	15.00	1.00	0.95	0.23	6.56		
				2	20.70	0.90	0.95	0.23	9.05		
			3rd cross		0.00	0.85			0.00		
				2	15.00	0.90	0.88	0.23	6.04		
				2	15.00	0.90	0.90	0.23	6.21		
				2	27.50	0.90	0.90	0.23	11.39		
			Ganesh layout Main road								
					0.00	5.80					
					15.00	6.80	6.30	0.23	21.74		
					15.00	6.50	6.65	0.23	22.94		
					15.00	5.40	5.95	0.23	20.53		
					4.00	4.80	5.10	0.23	4.69		
					0.00	19.20					
					8.80	17.00	18.10	0.23	36.63		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					0.00	17.00			0.00		
					15.00	13.60	15.30	0.23	52.79		
					15.00	9.50	11.55	0.23	39.85		
					15.00	6.70	8.10	0.23	27.95		
					15.00	7.70	7.20	0.23	24.84		
					0.00	7.70					
					5.40	7.90	7.80	0.23	9.69		
					2.50	5.90	6.90	0.23	3.97		
					15.00	4.80	5.35	0.23	18.46		
					8.30	4.90	4.85	0.23	9.26		
					0.00	4.90					
					11.00	7.30	6.10	0.23	15.43		
					15.00	4.10	5.70	0.23	19.67		
					15.00	4.80	4.45	0.23	15.35		
					15.00	4.80	4.80	0.23	16.56		
					15.00	4.90	4.85	0.23	16.73		
					12.00	7.50	6.20	0.23	17.11		
					0.00	7.50					
					15.00	4.00	5.75	0.23	19.84		
					15.00	5.40	4.70	0.23	16.22		
					15.00	4.30	4.85	0.23	16.73		
					15.00	5.50	4.90	0.23	16.91		
					15.00	6.20	5.85	0.23	20.18		
					15.00	4.70	5.45	0.23	18.80		
					15.00	4.70	4.70	0.23	16.22		
					15.00	4.70	4.70	0.23	16.22		
					15.00	4.60	4.65	0.23	16.04		
					15.00	5.40	5.00	0.23	17.25		
					5.40	7.30	6.35	0.23	7.89		
									1786.25		
									1786.25	1674.20	**2990538.00**

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
28	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 Kg / sqm using mechnical means complete as per specifications. MORTH specification NO. 502, **Page No. 160 / Item No. 21.6 / PWD SR 2015-16**	Sqm									
			Durga Temple Road								
					0.00	9.50					
					15.00	6.20	7.85		117.75		
					15.00	6.10	6.15		92.25		
					15.00	6.25	6.18		92.63		
					15.00	6.45	6.35		95.25		
					15.00	5.60	6.03		90.38		
					15.00	6.00	5.80		87.00		
					15.00	6.10	6.05		90.75		
					15.00	6.10	6.10		91.50		
					15.00	6.30	6.20		93.00		
					15.00	6.10	6.20		93.00		
					15.00	5.50	5.80		87.00		
					15.00	5.40	5.45		81.75		
					15.00	5.00	5.20		78.00		
					15.00	6.90	5.95		89.25		
					15.00	6.30	6.60		99.00		
					15.00	5.60	5.95		89.25		
					15.00	5.40	5.50		82.50		
					15.00	5.80	5.60		84.00		
					28.30	8.40	7.10		200.93		
			Basavasamithi layout								
			2nd 'A' cross		0.00	4.90					
					15.00	4.50	4.70		70.50		
					15.00	4.00	4.25		63.75		
					15.00	4.80	4.40		66.00		
					15.00	4.00	4.40		66.00		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	4.80	4.40		66.00		
					22.20	4.40	4.60		102.12		
			2nd 'B' cross		0.00	4.20					
					15.00	4.90	4.55		68.25		
					15.00	4.60	4.75		71.25		
					15.00	3.90	4.25		63.75		
					15.00	4.90	4.40		66.00		
					18.00	5.70	5.30		95.40		
			2nd 'C' cross		0.00	5.00					
					15.00	5.10	5.05		75.75		
					15.00	4.90	5.00		75.00		
					15.00	4.90	4.90		73.50		
					15.00	5.40	5.15		77.25		
					15.50	5.20	5.30		82.15		
			2nd 'D' cross		0.00	4.00					
					15.00	4.20	4.10		61.50		
					15.00	4.20	4.20		63.00		
					15.00	4.40	4.30		64.50		
					15.00	5.00	4.70		70.50		
					18.00	5.40	5.20		93.60		
			2nd cross road(West side)		0.00	5.20					
					15.00	5.20	5.20		78.00		
					15.00	5.00	5.10		76.50		
					15.00	5.25	5.13		76.88		
					15.00	5.00	5.13		76.88		
					15.00	4.70	4.85		72.75		
					17.80	5.20	4.95		88.11		
			2nd cross road(East side)		0.00	5.00					
					15.00	5.00	5.00		75.00		
					15.00	4.80	4.90		73.50		
					15.30	5.40	5.10		78.03		
			L.G.Enclave layout								
			Main Road		0.00	5.70					
					15.00	5.50	5.60		84.00		
					15.00	6.00	5.75		86.25		
					15.00	5.40	5.70		85.50		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	5.70	5.55		83.25		
					15.00	6.20	5.95		89.25		
					15.00	6.10	6.15		92.25		
					15.00	5.50	5.80		87.00		
					15.00	6.20	5.85		87.75		
					15.00	6.40	6.30		94.50		
					15.00	5.60	6.00		90.00		
					15.00	6.10	5.85		87.75		
					15.00	6.00	6.05		90.75		
					15.00	6.00	6.00		90.00		
					28.10	6.70	6.35		178.44		
			1st cross		0.00	6.60			0.00		
					15.00	6.50	6.55		98.25		
					15.00	6.30	6.40		96.00		
					23.00	7.30	6.80		156.40		
			2nd cross		0.00	5.60			0.00		
					15.00	5.70	5.65		84.75		
					15.00	5.80	5.75		86.25		
					20.70	7.20	6.50		134.55		
			3rd cross		0.00	4.50			0.00		
					15.00	5.00	4.75		71.25		
					15.00	5.00	5.00		75.00		
					27.50	5.50	5.25		144.38		
			Ganesh layout Main road								
					0.00	5.80			0.00		
					15.00	6.80	6.30		94.50		
					15.00	6.50	6.65		99.75		
					15.00	5.40	5.95		89.25		
					4.00	4.80	5.10		20.40		
					0.00	19.20					
					8.80	17.00	18.10		159.28		
					0.00	17.00			0.00		
					15.00	13.60	15.30		229.50		
					15.00	9.50	11.55		173.25		
					15.00	6.70	8.10		121.50		
					15.00	7.70	7.20		108.00		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					0.00	7.70					
					5.40	7.90	7.80		42.12		
					2.50	5.90	6.90		17.25		
					15.00	4.80	5.35		80.25		
					8.30	4.90	4.85		40.26		
					0.00	4.90					
					11.00	7.30	6.10		67.10		
					15.00	4.10	5.70		85.50		
					15.00	4.80	4.45		66.75		
					15.00	4.80	4.80		72.00		
					15.00	4.90	4.85		72.75		
					12.00	7.50	6.20		74.40		
					0.00	7.50					
					15.00	4.00	5.75		86.25		
					15.00	5.40	4.70		70.50		
					15.00	4.30	4.85		72.75		
					15.00	5.50	4.90		73.50		
					15.00	6.20	5.85		87.75		
					15.00	4.70	5.45		81.75		
					15.00	4.70	4.70		70.50		
					15.00	4.70	4.70		70.50		
					15.00	4.60	4.65		69.75		
					15.00	5.40	5.00		75.00		
					5.40	7.30	6.35		34.29		
									8846.45		
									8846.45	31.65	**279989.98**

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
29	KSRRB 500-11: Providing and laying **bituminous macadam** on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead lift and cost including lead, lift and cost of all materials, labour HOM of machineries complete as per specifications **using 40/60 TPH capacity H.M.P with Mechanical paver Gr-II (50 mm to 75 mm) with 3.3 % VG-30 Bitumen, Page No. 161 / Item No. 21.11.6/ PWD SR 2015-16**	Cum	**L.G.Enclave layout**							
			Main Road		0.00	5.70					
					15.00	5.50	5.60	0.05	4.20		
					15.00	6.00	5.75	0.05	4.31		
					15.00	5.40	5.70	0.05	4.28		
					15.00	5.70	5.55	0.05	4.16		
					15.00	6.20	5.95	0.05	4.46		
					15.00	6.10	6.15	0.05	4.61		
					15.00	5.50	5.80	0.05	4.35		
					15.00	6.20	5.85	0.05	4.39		
					15.00	6.40	6.30	0.05	4.73		
					15.00	5.60	6.00	0.05	4.50		
					15.00	6.10	5.85	0.05	4.39		
					15.00	6.00	6.05	0.05	4.54		
					15.00	6.00	6.00	0.05	4.50		
					28.10	6.70	6.35	0.05	8.92		
			Ganesh layout Main road								
					0.00	5.80			0.00		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	6.80	6.30	0.05	4.73		
					15.00	6.50	6.65	0.05	4.99		
					15.00	5.40	5.95	0.05	4.46		
					4.00	4.80	5.10	0.05	1.02		
					0.00	19.20					
					8.80	17.00	18.10	0.05	7.96		
					0.00	17.00			0.00		
					15.00	13.60	15.30	0.05	11.48		
					15.00	9.50	11.55	0.05	8.66		
					15.00	6.70	8.10	0.05	6.08		
					15.00	7.70	7.20	0.05	5.40		
					0.00	7.70					
					5.40	7.90	7.80	0.05	2.11		
					2.50	5.90	6.90	0.05	0.86		
					15.00	4.80	5.35	0.05	4.01		
					8.30	4.90	4.85	0.05	2.01		
					0.00	4.90					
					11.00	7.30	6.10	0.05	3.36		
					15.00	4.10	5.70	0.05	4.28		
					15.00	4.80	4.45	0.05	3.34		
					15.00	4.80	4.80	0.05	3.60		
					15.00	4.90	4.85	0.05	3.64		
					12.00	7.50	6.20	0.05	3.72		
					0.00	7.50					
					15.00	4.00	5.75	0.05	4.31		
					15.00	5.40	4.70	0.05	3.53		
					15.00	4.30	4.85	0.05	3.64		
					15.00	5.50	4.90	0.05	3.68		
					15.00	6.20	5.85	0.05	4.39		
					15.00	4.70	5.45	0.05	4.09		
					15.00	4.70	4.70	0.05	3.53		
					15.00	4.70	4.70	0.05	3.53		
					15.00	4.60	4.65	0.05	3.49		
					15.00	5.40	5.00	0.05	3.75		
					5.40	7.30	6.35	0.05	1.71		
									191.65		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
									191.65	6050.10	**1159511.00**
30	KSRRB 500-7: Providing and applying **tack coat** using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5, **No. 160 / Item No. 21.7 / PWD SR 2015-16**	Sqm									
			Durga Temple Main Road								
			Main Road		0.00	5.70					
					15.00	5.50	5.60		84.00		
					15.00	6.00	5.75		86.25		
					15.00	5.40	5.70		85.50		
					15.00	5.70	5.55		83.25		
					15.00	6.20	5.95		89.25		
					15.00	6.10	6.15		92.25		
					15.00	5.50	5.80		87.00		
					15.00	6.20	5.85		87.75		
					15.00	6.40	6.30		94.50		
					15.00	5.60	6.00		90.00		
					15.00	6.10	5.85		87.75		
					15.00	6.00	6.05		90.75		
					15.00	6.00	6.00		90.00		
					28.10	6.70	6.35		178.44		
			Ganesh layout Main road								
					0.00	5.80			0.00		
					15.00	6.80	6.30		94.50		
					15.00	6.50	6.65		99.75		
					15.00	5.40	5.95		89.25		
					4.00	4.80	5.10		20.40		
					0.00	19.20					
					8.80	17.00	18.10		159.28		
					0.00	17.00			0.00		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	13.60	15.30		229.50		
					15.00	9.50	11.55		173.25		
					15.00	6.70	8.10		121.50		
					15.00	7.70	7.20		108.00		
					0.00	7.70					
					5.40	7.90	7.80		42.12		
					2.50	5.90	6.90		17.25		
					15.00	4.80	5.35		80.25		
					8.30	4.90	4.85		40.26		
					0.00	4.90					
					11.00	7.30	6.10		67.10		
					15.00	4.10	5.70		85.50		
					15.00	4.80	4.45		66.75		
					15.00	4.80	4.80		72.00		
					15.00	4.90	4.85		72.75		
					12.00	7.50	6.20		74.40		
					0.00	7.50					
					15.00	4.00	5.75		86.25		
					15.00	5.40	4.70		70.50		
					15.00	4.30	4.85		72.75		
					15.00	5.50	4.90		73.50		
					15.00	6.20	5.85		87.75		
					15.00	4.70	5.45		81.75		
					15.00	4.70	4.70		70.50		
					15.00	4.70	4.70		70.50		
					15.00	4.60	4.65		69.75		
					15.00	5.40	5.00		75.00		
					5.40	7.30	6.35		34.29		
									3833.03		
									3833.03	14.77	**56614.00**

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
31	KSRRB M500-19: Providing and laying **bituminous concrete** 40mm thick with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH Specificationon NO. 509, **using 40/60 TPH capacity with Mechanical Paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen, Page No. 164 / Item No. 21.22.6/ PWD SR 2015-16**	Cum								
			Durga Temple Road								
					0.00	9.50					
					15.00	6.20	7.85	0.04	4.71		
					15.00	6.10	6.15	0.04	3.69		
					15.00	6.25	6.18	0.04	3.71		
					15.00	6.45	6.35	0.04	3.81		
					15.00	5.60	6.03	0.04	3.62		
					15.00	6.00	5.80	0.04	3.48		
					15.00	6.10	6.05	0.04	3.63		
					15.00	6.10	6.10	0.04	3.66		
					15.00	6.30	6.20	0.04	3.72		
					15.00	6.10	6.20	0.04	3.72		
					15.00	5.50	5.80	0.04	3.48		
					15.00	5.40	5.45	0.04	3.27		
					15.00	5.00	5.20	0.04	3.12		
					15.00	6.90	5.95	0.04	3.57		
					15.00	6.30	6.60	0.04	3.96		
					15.00	5.60	5.95	0.04	3.57		
					15.00	5.40	5.50	0.04	3.30		
					15.00	5.80	5.60	0.04	3.36		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					28.30	8.40	7.10	0.04	8.04		
			Basavasamithi layout								
			2nd 'A' cross		0.00	4.90					
					15.00	4.50	4.70	0.04	2.82		
					15.00	4.00	4.25	0.04	2.55		
					15.00	4.80	4.40	0.04	2.64		
					15.00	4.00	4.40	0.04	2.64		
					15.00	4.80	4.40	0.04	2.64		
					22.20	4.40	4.60	0.04	4.08		
			2nd 'B' cross		0.00	4.20					
					15.00	4.90	4.55	0.04	2.73		
					15.00	4.60	4.75	0.04	2.85		
					15.00	3.90	4.25	0.04	2.55		
					15.00	4.90	4.40	0.04	2.64		
					18.00	5.70	5.30	0.04	3.82		
			2nd 'C' cross		0.00	5.00					
					15.00	5.10	5.05	0.04	3.03		
					15.00	4.90	5.00	0.04	3.00		
					15.00	4.90	4.90	0.04	2.94		
					15.00	5.40	5.15	0.04	3.09		
					15.50	5.20	5.30	0.04	3.29		
			2nd 'D' cross		0.00	4.00					
					15.00	4.20	4.10	0.04	2.46		
					15.00	4.20	4.20	0.04	2.52		
					15.00	4.40	4.30	0.04	2.58		
					15.00	5.00	4.70	0.04	2.82		
					18.00	5.40	5.20	0.04	3.74		
			2nd cross road(West side)		0.00	5.20					
					15.00	5.20	5.20	0.04	3.12		
					15.00	5.00	5.10	0.04	3.06		
					15.00	5.25	5.13	0.04	3.08		
					15.00	5.00	5.13	0.04	3.08		
					15.00	4.70	4.85	0.04	2.91		
					17.80	5.20	4.95	0.04	3.52		
			2nd cross road(East side)		0.00	5.00					

C&FC. 22/12

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					15.00	5.00	5.00	0.04	3.00		
					15.00	4.80	4.90	0.04	2.94		
					15.30	5.40	5.10	0.04	3.12		
			L.G.Enclave layout								
			Main Road		0.00	5.70		0.04	0.00		
					15.00	5.50	5.60	0.04	3.36		
					15.00	6.00	5.75	0.04	3.45		
					15.00	5.40	5.70	0.04	3.42		
					15.00	5.70	5.55	0.04	3.33		
					15.00	6.20	5.95	0.04	3.57		
					15.00	6.10	6.15	0.04	3.69		
					15.00	5.50	5.80	0.04	3.48		
					15.00	6.20	5.85	0.04	3.51		
					15.00	6.40	6.30	0.04	3.78		
					15.00	5.60	6.00	0.04	3.60		
					15.00	6.10	5.85	0.04	3.51		
					15.00	6.00	6.05	0.04	3.63		
					15.00	6.00	6.00	0.04	3.60		
					28.10	6.70	6.35	0.04	7.14		
			1st cross		0.00	6.60			0.00		
					15.00	6.50	6.55	0.04	3.93		
					15.00	6.30	6.40	0.04	3.84		
					23.00	7.30	6.80	0.04	6.26		
			2nd cross		0.00	5.60			0.00		
					15.00	5.70	5.65	0.04	3.39		
					15.00	5.80	5.75	0.04	3.45		
					20.70	7.20	6.50	0.04	5.38		
			3rd cross		0.00	4.50			0.00		
					15.00	5.00	4.75	0.04	2.85		
					15.00	5.00	5.00	0.04	3.00		
					27.50	5.50	5.25	0.04	5.78		
			Ganesh layout Main road								
					0.00	5.80		0.04	0.00		
					15.00	6.80	6.30	0.04	3.78		
					15.00	6.50	6.65	0.04	3.99		
					15.00	5.40	5.95	0.04	3.57		

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
					4.00	4.80	5.10	0.04	0.82		
					0.00	19.20					
					8.80	17.00	18.10	0.04	6.37		
					0.00	17.00			0.00		
					15.00	13.60	15.30	0.04	9.18		
					15.00	9.50	11.55	0.04	6.93		
					15.00	6.70	8.10	0.04	4.86		
					15.00	7.70	7.20	0.04	4.32		
					0.00	7.70					
					5.40	7.90	7.80	0.04	1.68		
					2.50	5.90	6.90	0.04	0.69		
					15.00	4.80	5.35	0.04	3.21		
					8.30	4.90	4.85	0.04	1.61		
					0.00	4.90					
					11.00	7.30	6.10	0.04	2.68		
					15.00	4.10	5.70	0.04	3.42		
					15.00	4.80	4.45	0.04	2.67		
					15.00	4.80	4.80	0.04	2.88		
					15.00	4.90	4.85	0.04	2.91		
					12.00	7.50	6.20	0.04	2.98		
					0.00	7.50					
					15.00	4.00	5.75	0.04	3.45		
					15.00	5.40	4.70	0.04	2.82		
					15.00	4.30	4.85	0.04	2.91		
					15.00	5.50	4.90	0.04	2.94		
					15.00	6.20	5.85	0.04	3.51		
					15.00	4.70	5.45	0.04	3.27		
					15.00	4.70	4.70	0.04	2.82		
					15.00	4.70	4.70	0.04	2.82		
					15.00	4.60	4.65	0.04	2.79		
					15.00	5.40	5.00	0.04	3.00		
					5.40	7.30	6.35	0.04	1.37		
									353.86		
									353.86	9594.72	**3395166.51**

Sl. No	Full description,etc,of work	Unit		Number	Length	Breadth	Av Breadth	Depth	Quantity	Rate	Amount
37	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. **From 0.00 to 11.90 Km (PWD SR 2015-16** Rates P No 139)	Cum									
						Qty Vide Item No.2			**1887.91**	103.87	**196096.74**
	Certificate:										**15199617.00**

1. Certified that the above work done satisfactory and no materials issued from departmentally.
2. Certified that the Contractor has removed all debris from Work Spot.

Assistant Engineer
WardNo. 09
21/12/2017.

Assistant Executive Engineer
Vidyaranyapura Sub Division